BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work:Constructions of RCC Drains at 1st & 3rd Main Roads of Manjunathanagara in Ward No.14,

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	306.00	81.00	Rupees Eighty One Only
2	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	45.90	3812.82	Rupees Three Thousand Eight Hundred Twelve and Eighty Two Paise Only
3	Providing and laying in position plain cement concrete of design mix M20 with OPC cement @320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	114.75	5142.06	Rupees Five Thousand One Hundred Forty Two and Six Paise Only
4	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	61.97	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	765.00	239.56	Rupees Two Hundred Thirty Nine and Fifty Six Paise Only

Signature of the Contractor
Technical Manager(TM-2)
BBMP, Dasarahalli Zone, Bangalore

EXECUTIVE ENGINEER
Executive Engineer
Bruhat Bangalore Mahanagara Palike.

6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	255.00	1600.00	Rupees One Thousand Six Hundred Only
7	Lead for Disposal of Debris shall be payable at carage rates be mechanical means - With all lead, lifts, loading and unloading charges, cost and conveyance of all matrials, labour, equipments - 10Kmtrs etc. complete as per specifications.	Cum	295.00	78.24	Rupees Seventy Eight and Twenty Three Paise Only

Signature of the Contractor
Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer
Dasarahalli Division,
Dasarahalli Zone, Bangalore-57.